

Archer Western is seeking qualified DBE subcontractors and suppliers for the MDSHA US-40 over Gunpowder Falls Bridge Replacement Project. This project includes widening and superstructure replacement of Dual Bridges Nos. 0303403 and 0303404 carrying US 40 (Pulaski Highway) over Little Gunpowder Falls and Dual Bridges Nos. 0303503 and 0303504 carrying US 40 (Pulaski Highway) over Gunpowder Falls. The bridges over Little Gunpowder Falls are two (2) span, dual steel girder bridges approximately 95-feet in length and carry a 44'-3" wide roadway in each direction. The bridges over Gunpowder Falls are three (3) span, dual steel girder bridges approximately 193-feet in length and carry a 40'-9" wide roadway in each direction. The project includes removal and replacement of the existing concrete bridge deck, girder replacement, partial removal and widening of the substructure, concrete repairs to existing substructure to remain, approach roadway reconstruction, approach roadway grinding and resurfacing, relocation of the gas main at both stream crossings, concrete stop pad replacement, and construction of grass swales along the outside shoulder of US 40 eastbound. For a majority of construction, all lanes of traffic will be open but one lane of traffic in each direction will be closed during one stage of construction for 60 days while school is not in session.

This project bids on April 12, 2018 at 12:00 PM (ET).

Plans and Specs: <https://secure.smartbidnet.com/External/PublicPlanRoom.aspx?Id=357830>

All Subcontractor/Supplier quotes are due by **April 10, 2018**

Fax quotes to: (404) 495-8701 reference project name and scope of work.

For more information, please contact Joe Fortuchang, 404-495-8700 or jfortuchang@walshgroup.com

Scopes of work:

Quality Assurance	Quality Control
Testing and Inspecting Services	Traffic Control
Temporary Barriers and Enclosures	Temporary Erosion and Sediment Control
Construction Layout	Construction Surveying
Demolition	Concrete
Concrete Form Liners	Reinforcement Bars
Plain Steel Reinforcement Bars	Pumped Concrete
Precast Concrete	Concrete Cutting and Boring
Structural Steel for Bridges	Metal Decking
Metal Railings	Dampproofing and Waterproofing
Bridge Expansion Joint Cover Assemblies	Painting and Coating
Exterior Painting	Signage
Traffic Signage	Video Piping Inspections
Electrical	Aggregates for Earthwork
Geotextiles for Earthwork	Clearing and Grubbing
Soil Treatment	Soil Stabilization
Shoring and Underpinning	Anchor Tiebacks
Driven Piles	Steel H Piles
Cold Milling Asphalt Paving	Grooving of Concrete Paving / Decks
Bases, Ballasts, and Paving	Asphalt Paving
Curbs and Gutters	Pavement Markings
Fences and Gates	Retaining Walls
Planting	Turf and Grasses
Utilities	Cleaning of Sewers

Storm Drainage Utilities (Structures)

Pipe Culverts

Vehicle Median Barriers

Vehicle Traffic Barriers

Bridge Specialties

Flatbed Trucks

Roadway Rumble Strips

Storm Utility Drainage Piping

Subdrainage

Vehicle Crash Barriers

Vehicle Guide Rails

Dump Trucks

Demolition/Blasting

Quotes will be evaluated on scope, price, experience, financial condition, and other pertinent factors.